

Prepared for:
Boulder County, Colorado

Flood Planning & Preliminary Design Services for South St. Vrain Creek Restoration at Hall Ranch **Presentation to Parks and Open Space Advisory Committee**

September 22, 2016




In association with:
Otak, THK, ERO, and Blue Mountain



Introductions

- 🏗️ Introduction
- 🏗️ History of project
- 🏗️ Planning area: 3.2 Mile Reach from Canyon to Bridge
- 🏗️ Project sponsors and funding: DOLA/BCPOS
 - 30% Report and Designs
 - EWP Eligible Construction
- 🏗️ Project website
 - Information and comment
 - www.BoulderCountyOpenSpace.org/ssv






Matrix
DESIGN GROUP





Matrix Team



PROJECT TEAM			
STAKEHOLDER ENGAGEMENT Kevin Shanks, RLA, ASLA ^(THK) Robert Krehbiel, PE ^(Matrix)	HYDROLOGY AND HYDRAULICS Robert Krehbiel, PE ^(Matrix) Scott Schreiber, PE ^(Matrix) Ho Hung-Teng, PE ^(Matrix)	CHANNEL RESTORATION DESIGN Blair Vajda, PE ^(Otak) Kevin Pilgrim ^(Otak) Scott Schreiber, PE ^(Matrix)	REVEGETATION Kevin Shanks, RLA, ASLA ^(THK) Julie Gamec, RLA ^(THK) Brandon Parsons, ASLA ^(THK)
SURVEY SERVICES Bob Meadows, PLS ^(Matrix)	FLUVIAL GEOMORPHOLOGY Luke Swan ^(Otak) Tracy Emmanuel ^(Otak)	FISHERY BIOLOGY Jim Nankervis ^(Blue)	RIPARIAN AND WETLAND ASSESSMENTS Clint Henke ^(ERO)





Project Schedule

Design schedule

- Notice to proceed: May 2016
- Alternative analysis: June 2016
- Preferred alternative: July 2016
- 30% design: September 2016
- EWP Permitting and 80% Design: Fall/Winter 2016
- EWP Construction: Winter/Spring 2017





Public Engagement

Extensive Public Engagement

- South St. Vrain Working Group – May 11
- St. Vrain Creek Coalition – May 25, June 29, July 20, and August 17
- General Public Meetings (Lyons) – May 24 and June 30
- Individual Land Owner Meetings – June 22
- Public Preferred Alternative Site Tour – July 28
- Various on-line comments, phone calls, and field visits

Comments since 2013





Pre Flood Aerial: 2012





Post Flood Aerial: 2013



Google earth

Imagery Date: 10/6/2013 40°12'04.43" N, 105°17'56.62" W, elev: 5359 ft, eye alt: 6463 ft



Post Flood Aerial: 2014



Imagery Date: 10/6/2014 40°12'04.45" N, 105°17'56.62" W, elev: 5353 ft eye alt: 6463 ft



Post Flood Aerial: 2015





Pre Flood Aerial: 2012





Post Flood Aerial: 2013



Google earth

Imagery Date: 10/6/2013 40°12'35.59" N -105°16'58.30" W elev: 5424 ft eye alt: 6343 ft



Post Flood Aerial: 2014





Post Flood Aerial: 2015





Pre Flood Aerial: 2012





Post Flood Aerial: 2013



Google earth

Imagery Date: 10/6/2013... 40°12'51.88" N, 105°16'34.70" W, elev: 5403 ft, eye alt: 6014 ft



Post Flood Aerial: 2014






Post Flood Aerial: 2015





Project Goals Statement

- Provide a conceptual design for the entire South Saint Vrain Creek project area that restores and improves the channel and surrounding floodplain areas to a safe, natural, resilient, functioning, and ecologically rich habitat. This project will use qualitative research, quantitative data, and community input to inform resilient design that shall utilize natural system principles and onsite materials to expedite recovery from the 2013 floods and set up for better performance in future flood events. Components to meet goals include incorporating natural channel diversity and character, re-establishing floodplain benches for lateral connectivity, reducing longitudinal connectivity constraints, improving flow conveyance and sediment transport to maintain environmental values, promote naturally functioning stream processes, protect public and private infrastructure, improve public safety, repair unstable erosion scars in high-risk areas, and revegetate denuded areas.





Decision Making Process

South St. Vrain Creek Restoration at Hall Ranch Decision Making Process:

Project Goals



Parks & Open Space

Provide a conceptual design for the entire South Saint Vrain Creek project area that restores and improves the channel and surrounding floodplain areas to a safe, natural, resilient, functioning, and ecologically rich habitat. Provide a preliminary design for the EWP project reaches. This project will use qualitative research, quantitative data, and community input to inform resilient design that shall utilize natural system principles and onsite materials to expedite recovery from the 2013 floods and set up for better performance in future flood events. Components to meet goals include incorporating natural channel diversity and character, re-establishing floodplain benches for lateral connectivity, reducing longitudinal connectivity constraints, improving flow conveyance and sediment transport to maintain environmental values, promote naturally functioning stream processes, protect public and private infrastructure, improve public safety, repair unstable erosion scars in high-risk areas, and revegetate denuded areas.

Core Values

Community

- Communicates with the residents
- Incorporate residents needs in alternative analysis
- Be mindful of impact of property value
- Consider the affects work will have downstream
- Consider recreational opportunities
- Increase aesthetic appeal
- Consider existing water rights
- Minimize impact to cultural and historic features

Resiliency

- Improve "Creek Conveyance"
- Provide smarter infrastructure solutions
- Improve creek stability
- Reduce risk to critical infrastructure
- Restore natural ecosystem process
- Reconnect the floodplain

Safety

- Reduce the impacts to private property
- Reduce potential flood risk
- Make public safety top priority

Environment

- Assess existing environmental conditions
- Reduce sedimentation in general
- Improve wildlife habitat (banking opportunities)
- Increased channel capacity to accommodate future flooding
- Work with natural systems
- Improve fish passage and habitat
- Remove and recycle onsite materials
- Avoid highly-engineered solutions
- Re-establish natural condition of the channel and adjacent stream bank
- Increase revegetation efforts
- Concerned about movement of potential debris both short and long term
- Concerned about ground water and the rise in the creek bed elevation
- Concerned about interim berm condition along creek
- Consider new 100 year hydrologic volumes

Implementation

- Work with existing project initiatives and ongoing projects
- Find funding for future implementation
- Include fiscally responsible costs
- Continue longterm planning for future projects
- Meet the goals for EWP funding
- Consider elements of the master plan
- Be consistent with land use regulations and management
- Consider phasing

Schedule

- Prioritize strategies as critical, necessary or desired

Prioritization Criteria

1. Protect critical public and private infrastructure?
2. Avoids negative impacts to downstream infrastructure, channel and stormwater systems?
3. Improves aesthetics to the creek corridor?
4. Consider recreation where allowed?

5. Benefits larger area of creek corridor?
6. Re-establishes floodplain connectivity?
7. Restores affected areas of the South St. Vrain Creek channel and surrounding areas to stable, resilient and ecologically rich habitats?
8. Reduces future recovery time?
9. Improves conveyance of sediment?

10. Reduce flood risk to the public and residents by providing long term solutions that increase resiliency?

11. Natural ecosystem processes restored?
12. Protects or improves existing habitat and significant ecological resources?
13. Incorporates locally available materials and environmentally friendly processes?
14. Protects and improves water quality and the geomorphology of the creek?

15. Creates infrastructure investments that are reasonable to construct and provides the best value for their life-cycle, function and purpose?
16. Can be supported by current land use regulations or revised land use regulations?
17. Provides funding, partnering and collaboration opportunities by meeting multiple stakeholder objectives?



Comments/Concerns



Core Values



Project Goals



Prioritization Criteria



Prioritization Criteria

SOUTH ST. VRAIN CREEK RESTORATION AT HALL RANCH DECISION MATRIX - FOR THE PRIORITIZATION OF THE PREFERRED ALTERNATIVE 7/12/2016

ID	Critical Issues	Prioritization Criteria	Alternatives Evaluation			
			Floodplain Connectivity	Channel Complexity	Revegetation	Infrastructure Protection
<i>Prioritization Criteria</i>						
1	Community	Protect critical public and private infrastructure?	The best way to increase flood volume and reduce flood energy throughout the system. Note: (Detention ponds can not provide enough volume to mitigate flood impacts. Water rights are needed to detain water. Detention ponds would fill full of sediment. There is typically not enough room to detain the appropriate amount of water needed.)	Can provide some channel stability.	Once vegetation is established can provide some flood plain stability.	Can provide immediate site specific protection to infrastructure. No system wide mitigation.
2	Community	Avoids negative impacts to downstream infrastructure, channel and storm water systems?	Returns the river corridor to a more natural channel condition with minimal downstream impacts.	Minimal downstream negative impacts.	Minimal downstream negative impacts.	While the technique might provide protection for the immediate element of infrastructure being protected, the technique can cause negative impacts downstream.
3	Community	Improves aesthetics to the creek corridor?	Returns the river corridor to a more natural channel condition. Time needed for naturalization of vegetation.	Improves the aesthetics of the channel.	Jump starts revegetation of the entire river corridor.	Most techniques appear engineered.
4	Community	Consider recreation where allowed? ^[1]	Improves the quality of the recreational experience.	Provides instream structures that could act as a recreational amenity to kayakers and fishermen.	Improves the quality of the recreational experience.	Recreational objectives could be included with infrastructure protection.
5	Resiliency	Benefits larger area of creek corridor?	Benefits the larger creek corridor by jump starting the natural systems.	Benefits the channel by moderating sediment load.	Benefits the larger creek corridor but without floodplain connectivity the results will be diminished.	Very site specific benefits at the point where the improvement is made.
6	Resiliency	Re-establishes floodplain connectivity?	Yes. Floodplain connectivity is the most holistic approach to re-establish a functioning floodplain.	Yes. Channel complexity would contribute to inundation of floodplain benches.	Yes. Revegetation provides roughness to slow floodwater down and establishes long lasting ecosystem benefits.	No.
7	Resiliency	Restores affected areas of the South St. Vrain Creek channel and surrounding areas to stable, resilient and ecologically rich habitats?	Yes.	Yes.	Jump starts terrestrial and riparian habitat.	Makes certain reaches more stable.
8	Resiliency	Reduces future recovery time?	Jump starts the natural systems of the corridor most holistic approach.	Not a holistic approach, focuses on channel.	Not a holistic approach. Some established vegetation, soil structure and seedbanks would survive a flood event and secondary succession would occur.	Not a holistic approach. Infrastructure protection would protect existing features and reduce future work needed after a flood event.
9	Resiliency	Moderates conveyance of sediment?	Yes for the entire reach.	Yes for the entire reach.	Traps sediment during a flood and minimizes erosion.	Could be part of the strategy at diversions, bridges and culverts.
10	Safety	Reduce flood risk to the public and residents by providing long term solutions that increase resiliency?	Increases flood storage volume and reduces flood energy throughout the system.	Provides some creek channel resiliency.	Once allowed to mature the vegetation provides some resistance to future floods.	Hardened points are created in the corridor not always resilient.
11	Environment	Natural ecosystem processes restored?	Most holistic approach.	Partial approach, not all ecosystems addressed.	Partial approach, not all ecosystems addressed.	Least holistic approach.
12	Environment	Protects or improves existing habitat and significant ecological resources?	Improves both terrestrial and aquatic habitat.	Improves aquatic habitat.	Improves terrestrial and riparian habitat.	Not the focus of infrastructure protection techniques.
13	Environment	Incorporates locally available materials and environmentally friendly processes?	Not a differentiator. All alternatives can incorporate locally available materials and environmentally friendly processes.			
14	Environment	Protects and improves water quality and the geomorphology of the creek?	Protects geomorphology and jump starts natural systems of the creek.	Protects geomorphology and jump starts natural systems of the creek.	Reduces erosion.	Reduces erosion in site specific areas.
15	Implementation	Creates infrastructure investments that are reasonable to construct and provides the best value for their lifecycle, function and purpose?	Because it jump starts the corridor's natural systems it is the best value for their life-cycle.	Reasonable to construct and jump starts natural systems of the creek.	Without regrading, the revegetation effort will have diminished results.	Protects infrastructure but requires on-going maintenance.
16	Implementation	Can be supported by current land use regulations or revised land use regulations?	Not a differentiator. All alternatives can be supported by the current land use regulations.			
17	Implementation	Provides funding, partnering and collaboration opportunities by meeting multiple stakeholder objectives?	Not a differentiator. There are opportunities with all alternatives for partnering.			
Notes:						
Definitions: Fair - What is thought to be right acceptable Better - Higher in quality Best - Better than all others in quality or value						




Alternatives evaluated in matrices to determine most effect (preferred) alternative





Alternative: Floodplain Connectivity





Alternative: Revegetation


Cotton Wood Gallery



Wetland/Riparian Bench




Grassland Meadow







Alternative: Infrastructure Protection




Utility Armoring



Root Wad Stabilization



Boulder Toe Protection



Vegetated Geogrid





Additional Design Aspects Evaluated

Existing infrastructure aspects investigated to provide future recommendations

Old St Vrain Road Bridge

- Required capacity and road overtopping

Longmont Diversion

- Relocation of diversion and floodplain conveyance

South Ledge/Meadows Ditch

- Sedimentation issues

Woody Vegetation Management





Geomorphology

■ Geomorphic Assessment


- Data Review
- Desktop Analysis
- Field Assessment

■ Sediment Transport

- Stability Analyses
- Trajectory determination
- Structure design


■ What questions are we trying to answer?

- What are prevailing processes and how do we use them to achieve the project goals?
- What is the channel trajectory and what does that mean for the project goals?
- Is the channel stable? Is the design stable?






Geomorphology - Assessment



Google earth



Geomorphology - Assessment





Geomorphology - Assessment

River Styles

Partially Confined, Alluvial Valley (PCAV)

Properties:

The majority of the reaches in the study area are classified under this stream style. They occupy the transition from the canyons through the hogbacks to the alluvial plain landscape units. Slopes are steep, but milder than the confined reaches (observed slopes ranged from 0.3% to 2.1%). As a result of this relative steepness, relative lack of confinement, and position downstream of confined reaches directly coupled with hillslope sediment supplies, these reaches exhibit the most geomorphic response to floods. Because these reaches experienced the most geomorphic change, many channels of this style are still evolving in response to the floods. In some cases, channels are beginning to narrow and some side channels are slowly filling in with sediment. Nevertheless, a large amount of unstable sediment ranging from sand to cobble material exists in the banks and floodplains of these reaches and will continue to be a net sediment supply to downstream reaches for some time.

Reaches:

SVC-03, SVC-04, SVC-05 / NSV-04, NSV-05, NSV-06 / SSV-03, SSV-04, SSV-05, SSV-06, SSV-07, SSV-08, SSV-09



RIVER CHARACTERISTICS

Valley Setting	Partially confined. Observed confinement ratio ranging from 3 to 35
Channel Planform	Meandering channel with low sinuosity, braided in some areas after flood. High flow, side channels present.
Bed Morphology	Typical: pool-riffle, boulder clusters, large wood jams and roughness elements; lateral and mid-channel bars Observed: pool-riffle, plane bed, riffle-run, mid-channel/point/lateral bars, instream large wood

RIVER BEHAVIOR


Current Stream Evolution Stage	Majority of reaches are in the Aggradation and Widening stage, with a few in the Degradational stage and a few in the Quasi Equilibrium stage (post-restoration)
Flood Response	Flood response ranged from channel widening throughout, downstream lateral migration of meander bends, channel avulsion, and braiding.
Stage Behavior	Low flows are generally single thread with splits around mid-channel bars. Sediment is stored in bar complexes at the channel margin. Bankfull flows activate side channels and re-work in-channel bars. Large wood has significant influence on bank erosion and sediment accumulation. At flood stages, extremely high stream power values are generated before flows can spill into extensive floodplains, dissipating stream energy. Side channels are activated through inundation and channel avulsions will likely occur. Large wood is recruited into the channel as banks and terraces become undercut and may have significant influence over channel behavior as additional wood is racked up.





Geomorphology – Sediment Transport

Base Bed Mobility






Geomorphology – Sediment Transport

Effective Discharge

- Q_{eff} – flow that transports most sediment over time
- Q_h – discharge associated with cumulative 50% of sediment yield





Geomorphology – Sediment Transport

🏗️ Sediment Transport Capacity and Balance

Stream Power

$$q_s = 4.610^{-7} \Omega^{1.75} D_{50}^{-0.56}$$

$$\Omega = \frac{\omega^{1.5}}{R^3} \quad \omega = \frac{\rho g Q S}{b}$$

• Meyer-Peter Muller

$$\left(\frac{k_s}{k_r}\right)^{1/2} \gamma R S = 0.047(\gamma_s - \gamma) d_m + 0.25 \left(\frac{\gamma}{g}\right)^{1/4} \left(\frac{\gamma_s - \gamma}{\gamma_s}\right)^{2/3} g^{2/3}$$

- Where:
- g_s = Unit sediment transport rate in weight/time/
 - k_r = A roughness coefficient
 - k_s = A roughness coefficient based on grains
 - γ = Unit weight of water
 - γ_s = Unit weight of the sediment
 - g = Acceleration of gravity
 - d_m = Median particle diameter
 - R = Hydraulic radius
 - S = Energy gradient






Capacity-Supply Ratio (CSR)

- Reach capacity/supply
- 1 is good



Geomorphology – Sediment Transport


Sediment Transport Capacity and Balance





Geomorphology – Sediment Transport

🏗 Sediment Transport Capacity and Balance



Reach #	Expanded Area Study Reach ID	CSR at Q2
R8	SSV-10	N/A
R7	SSV-09	N/A
R6	SSV-08	2.8
R5	SSV-07	0.4
R4	SSV-06	0.6
R3	SSV-05	1.9
R2	SSV-04	2.3
R1	SSV-03	1.2
-	SSV-02	0.2
-	SSV-01	3.4





Geomorphology - SEM


Stream Evolution Model

Reach #	Expanded Study Reach ID	River Style	Current Stream Evolution Stage ^{a,b}	Capacity/Supply Ratio @ Q ₂		Stream Evolution Trajectory ^{a,b}	
				Existing	Proposed	Existing	Proposed
8	SSV-10	Confined Valley w/ FP pockets	N/A	-	-	N/A	N/A
7	SSV-09	Partially Confined, Alluvial Valley	Stage 3 Degradation	-	-	Stage 4 Degradation and Widening	Stage 6 Quasi Equilibrium
6	SSV-08	Partially Confined, Alluvial Valley	Stage 5 Aggradation and Widening	2.8	1.5	Stage 3 Degradation	Stage 4 Degradation and Widening
5	SSV-07	Partially Confined, Alluvial Valley	Stage 4 Degradation and Widening	0.38	0.4	Stage 5 Aggradation and Widening	Stage 6 Quasi Equilibrium
4	SSV-06	Partially Confined, Alluvial Valley	Stage 5 Aggradation and Widening	0.59	1.0	Stage 6 Quasi Equilibrium ^c	Stage 6 Quasi Equilibrium
3	SSV-05	Partially Confined, Alluvial Valley	Stage 4 Degradation and Widening	1.9	1.2	Stage 5 Aggradation and Widening ^c	Stage 7 Laterally Active
2	SSV-04	Partially Confined, Alluvial Valley	Stage 4 Degradation and Widening	2.3	1.3	Stage 5 Aggradation and Widening ^c	Stage 7 Laterally Active
1	SSV-03	Partially Confined, Alluvial Valley	Stage 5 Aggradation and Widening	1.2	1.2	Stage 6 Quasi Equilibrium ^c	Stage 3s Arrested Degradation

Notes: ^a Based on (Cuer & Thorne, 2013)

^b N/A=stream evolution model not applicable (e.g., step-pool reaches do not necessarily follow the same disturbance model)


^c Potential for reach to move into Stage 3 - Degradation





Geomorphology - Summary

- 🏗️ Stream is generally featureless, over-widened and likely to degrade disconnecting further from the existing floodplain
- 🏗️ Restoration and Flood Mitigation Strategies:
 - Establish equilibrium channel geometries that promote/maintain floodplain connection
 - Control sediment supply with aggressive revegetation
 - Establish geomorphic complexity to manage sediment load, improve habitat





Design Process

Understand Hydraulics with Development of Design Models

- 1-D HEC-RAS
 - Regulatory floodplain modeling
- 2-D Sedimentation and River Hydraulics
 - Final design parameters and sediment transport

Iterative Process

- EC Topography and Modeling
- PC Grading and PC Modeling 
- Refine PC Topography 
- Verify Capacity-Supply Ratio
- Structure and Revegetation Design





30% Design

Channel Geometry


- Function of hydraulic geometry, and constraints

Main Channel and Overflow Planform

- Pre-Flood or Existing Alignments

Channel Profile

- Equilibrium bed slope analysis (0.8 – 2% range)






30% Design


Channel and Floodplain Dimensions

Multi-Stage Channel




TYPICAL MAIN CHANNEL GRADING SECTION FOR STRAIGHT REACHES
NOT TO SCALE

TYPICAL MAIN CHANNEL GEOMETRY (ft)					
REACH TYPE	DIMENSION	NARROW	TYP	WIDE	
STRAIGHT REACH	Wbr	40	48	55	
	Wbed	31	38	44	
	Wp	25	29	32	
	Dp	2.5	2.25	2.1	
	Dp	0.84	0.76	0.73	
MEANDER REACH	Wbr	21	15.9	19	
	Wp	22	3	4	
	Dp	4.4	4.0	3.6	
	Dp	2.75	2.5	2.25	
	Dp	2.1	0.2	8.3	
		22	3	4	5
		23	2.5	3	3



TYPICAL MAIN CHANNEL GRADING SECTION FOR MEANDER REACHES
NOT TO SCALE



TYPICAL FLOODPLAIN GRADING SECTION
NOT TO SCALE







1.5 and 5 Year Overflow Channels

- 🏗️ Along Existing and/or Pre-Flood Channel Alignments to stretch implementation funds
- 🏗️ On Average 25' Bottom Width with Gentle Side Slopes
- 🏗️ Vegetation Lined and/or Stream Substrate





Riffle Structure Design





Large Woody Material and Vegetation

- Geomorphic, Biologic and Ecologic Benefits
- Implementation Guidance
 - Site Visit with Boulder County Emergency Management (OEM)
 - OEM Decision Process
 - Focused on hazard trees in the vicinity of infrastructure
 - National Guidance Documents on the Design of Engineered Log Structures






Large Wood Structure Design

Site ID	Structure Type	Structure Position	Meander	Station	d_w (ft)	R_w/W_{DF}	W_{max} (ft/s)
Lower R2A	Rootwad	Left bank	Straight	8+00	10.00	128.21	8.00

Multi-Log Structures	Layer	Log ID
Key Log	Large RW	

Channel Geometry Coordinates		
Proposed	x (ft)	y (ft)
Fidpin LB	0.00	5,309.00
Top LB	43.16	5,308.05
Toe LB	57.16	5,301.05
Thalweg	65.00	5,301.00
Toe RB	110.09	5,302.00
Top RB	149.66	5,307.37
Fidpin RB	192.38	5,309.29


Proposed Cross-Section and Structure Geometry (Looking D/S)



Wood Species	Rootwad	L_T (ft)	D_{T1} (ft)	L_{T2} (ft)	D_{T2} (ft)	T_{T1} (lb/ft ²)	T_{T2} (lb/ft ²)
Cottonwood, Eastern	Yes	30.0	2.00	3.00	6.00	28.0	50.0

Structure Geometry	θ (deg)	β (deg)	Define Fixed Point	x_T (ft)	y_T (ft)	$y_{T,max}$ (ft)	$y_{T,min}$ (ft)	A_{TP} (ft ²)
	45.0	0.0	Root collar: Bottom	59.00	5,301.00	5,299.00	5,305.00	25.63

Soils	Material	γ_s (lb/ft ³)	γ'_s (lb/ft ³)	ϕ (deg)	Soil Class	$L_{1,max}$ (ft)	$d_{0.05,max}$ (ft)	$d_{0.85,avg}$ (ft)
Stream Bed	Very coarse gravel	131.2	61.7	40.0	5	0.00	0.00	0.00
Bank	Gravel/sand	111.7	69.5	39.0	5	18.89	5.13	3.17



Lower R2A Rootwad Key Log Log ID Large RW Page 2

Vertical Force Analysis

Net Buoyancy Force						Lift Force	
Wood	V_{TL} (ft ³)	V_{RW} (ft ³)	V_T (ft ³)	W_T (lbf)	F_B (lbf)	C_{LT}	0.00
↑WSE	0.0	0.0	0.0	0	0	F_L (lbf)	0
↓WS↑Thw	84.8	25.5	110.3	3,083	6,882	F_B (lbf)	7,332
↓Thalweg	0.0	7.2	7.2	361	450	W_T (lbf)	3,444
Total	84.8	32.7	117.5	3,444	7,332	F_{soil} (lbf)	8,275

Soil Ballast Force				
Soil	V_{dry} (ft ³)	V_{sat} (ft ³)	V_{soil} (ft ³)	F_{soil} (lbf)
Bed	0.0	0.0	0.0	0
Bank	0.0	119.0	119.0	8,275
Total	0.0	119.0	119.0	8,275

Vertical Force Balance	
F_L (lbf)	0
F_B (lbf)	7,332
W_T (lbf)	3,444
F_{soil} (lbf)	8,275
$F_{W,V}$ (lbf)	0
$F_{A,V}$ (lbf)	0
ΣF_V (lbf)	4,386
FS_V	1.60

Horizontal Force Analysis

Drag Force						Horizontal Force Balance	
A_{TP} / A_{WV}	F_{TL}	C_{DL}	C_{Dv}	C_{D^*}	F_D (lbf)	F_D (lbf)	1,900
0.02	1.00	1.12	0.03	1.19	1,900	F_P (lbf)	18,185

Passive Soil Pressure		Friction Force	
Soil	K_p	F_P (lbf)	F_f (lbf)
Bed	4.60	0	877
Bank	4.40	18,185	2,706
Total	-	18,185	3,583

Horizontal Force Balance	
F_D (lbf)	1,900
F_P (lbf)	18,185
F_f (lbf)	3,583
$F_{W,H}$ (lbf)	0
$F_{A,H}$ (lbf)	0
ΣF_H (lbf)	19,868
FS_H	11.46

Moment Force Balance

Driving Moment		Resisting Moment Centroids		Moment Force Balance	
C_{TB} (ft)	C_L (ft)	C_D (ft)	C_{TW} (ft)	C_{soil} (ft)	C_{FAN} (ft)
18.3	0.0	24.5	18.3	9.4	15.0

Moment Force Balance	
M_D (lbf)	180,729
M_r (lbf)	487,498
FS_M	2.70

*Distances are from the stem tip Point of Rotation: Stem Tip

Anchor Forces

Additional Soil Ballast					Mechanical Anchors			
V_{dry} (ft ³)	V_{sat} (ft ³)	C_{soil} (ft)	$F_{A,soil}$ (lbf)	$F_{A,HP}$ (lbf)	Type	C_{An} (ft)	Soils	F_{An} (lbf)
			0	0				0



Boulder Ballast									
Position	D_L (ft)	C_{An} (ft)	V_{dry} (ft ³)	V_{sat} (ft ³)	W_r (lbf)	$F_{L,r}$ (lbf)	$F_{D,r}$ (lbf)	$F_{A,V,r}$ (lbf)	$F_{A,H,r}$ (lbf)
								0	0
								0	0
								0	0

Lower R2A Rootwad Key Log Log ID Large RW Page 3





Large Wood Structure Design




Matrix
DESIGN GROUP






Bank Stabilization

Mesh Module Vel_Mag_ft_p_s 0 15:00:00



Rasters




Matrix
DESIGN GROUP

otak

TK
associates, inc.






Bank Stabilization



- NOTES
1. INTEGRATE STAKE PLANTING TECHNIQUES DURING ROCK PLACEMENT TO ENSURE CONTACT WITH NATIVE GROUND
 2. PLACE SOIL FILL AROUND CUTTINGS AND WATER IN IF NEEDED
 3. ASSUME 15 STAKES PER LINEAR FOOT OF VEGETATED REINFORCED SOIL SLOPES

VEGETATED REINFORCED SOIL SLOPES


SCALE: N.T.S.



- NOTES
1. MAKE CLEAN CUTS AND DO NOT DAMAGE STAKES OR SPLIT ENDS
 2. DURING INSTALLATION USE A PILOT BAR IN FIRM SOILS
 3. TAMP THE SOIL AROUND THE STAKE / OR BACK FILL WITH MUD SLURRY.
 4. COLLECT WILLOWS FROM ONSITE TO CONSTRUCT WILLOW FASCINES.

LIVE WILLOW FASCINE

SCALE: N.T.S.



- NOTES
1. SEE REVEGETATION PLANS FOR LOCATIONS.

BOULDER TOE WILLOW PLANTING

SCALE: N.T.S.

Matrix DESIGN GROUP





Bank Stabilization




Matrix
DESIGN GROUP





Revegetation: Goals

- 🏗️ Preserve Existing Vegetation
- 🏗️ Planting Diversity Based Upon Proximity to Water Table (Iterative Design Process)
- 🏗️ Match existing plant species and ecosystem types to historical character and onsite conditions.





Revegetation Recommendations

🏠 Re-establish upland, riparian, wetland environments through:

- Seeding (Riparian and Upland)
- Perennial Tubelings
- Wetland Sod
- Tree and Shrub Plantings
- Willow Staking





Revegetation Results



Matrix
DESIGN GROUP





30% Design Plans and Report

Posted to Boulder County Project Website

- <http://www.bouldercounty.org/ssv>

30% Design Plans

- 62 Sheets
 - Plan and Profile of Main and Overflow Channels
 - Channel Design Details
 - Revegetation Plans
 - Revegetation and Bio-Engineering Details
 - Additional Planning Elements

30% Preliminary Basis of Design Report

- 299 Pages





Next Steps

80% Design Drawings

- Working with EWP and Boulder County
Currently to contract for additional services

Permitting

- 404 CWA, Floodplain, Land Use, Stormwater

Construction

- Bid Support
- Construction Oversight and Closeout

